



**INVITATION FOR BID (IFB) No. PAG-CIP-022-007
PAINTING OF EXTERIOR, INTERIOR, AND ROOF COATING
OF THE PAG CFS BUILDING**

AMENDMENT NO. 2

Date: August 2, 2022

ALL BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT ON THE AREA PROVIDED BELOW AND RETURN A COPY TO PAG PROCUREMENT OFFICE:

Fax: (671) 472-1439 or Email: pagprocurement@portofguam.com, Annie L.G. Sablan algsablan@portofguam.com, Mark A. Cabrera macabrera@portofguam.com and Denise Calvo djcalvo@portofguam.com.

NOTICE TO BIDDERS: The IFB documents of the above-referenced project are hereby AMENDED TO INCLUDE the following as part of IFB documents:

- 1. Amend to revise "Bid Schedule" found on pages 79 of 84 of the IFB. See attached.**

***** END OF AMENDMENT NO. 2, ALL OTHERS REMAIN THE SAME *****

Issued by:

RORY J. RESPICIO
GENERAL MANAGER

Acknowledgment Receipt

COMPANY NAME: _____

AUTHORIZED SIGNATURE: _____

PRINT NAME: _____

DATE / TIME _____ / _____

REVISED BID SCHEDULE for IFB-PAG-CIP-022-007

Item#	DESCRIPTION	QTY	UNIT	UNIT COST	EXTENDED COST
1	Mobilization	1	LS		
2	Site Safety/Environmental Control/Site Clean up	1	LS		
3	Water Blasting the entire building surfaces (Roof, Exterior, & Open Interior except for the interior of enclosed spaces)	1	LS		
4	Apply one (1) coat of primer paint and two (2) coats of UV/Mildew Resistant silicon-based coating on the entire roof.	40,500	SF		
5	Apply one (1) coat of primer paint and two (2) coats of acrylic semi-gloss UV/Mildew Resistant exterior/ interior grade paint on all surfaces of the building (exterior plus Interior).	100,000	SF		
6	Install new safety sign logos in 4'x 8'x 1/8" thick 316 stainless steel sheet. Anchoring using 316 stainless steel fasteners property to the concrete wall	10	EA.		
7	Plaster the surfaces with severe honeycombing. The estimated total area of concern is provided at 1,000 square feet. Please provide the unit cost.	1,000	SF		
8	Water Rate (Vendor to provide quantity)		Per 1,000 Gallons	\$32.73	
9	Concrete Crack Repair		Feet		
10	Concrete Spall Repair		CF		
GRAND TOTAL COST					

All unit costs Include Proper Disposal of Debris, Materials/Labor/Tools/Equipment/OH/Profit & Tax.

Note:

Grand Total cost shall be all-inclusive for a finished product, including Close Out Documents, etc.

Awarded Contractor shall provide a detailed Schedule of values for Progress Billing Purposes.