



**INVITATION for BID
IFB-PAG-CIP-021-005**

WATERLINE REPLACEMENT PROJECT

**AMENDMENT NO. 3
DATE: November 23, 2021**

ALL BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT ON AREA PROVIDED BELOW AND RETURN COPY TO PAG PROCUREMENT OFFICE:

Fax: (671) 472-1439 or Email: spmuna01@portofguam.com, pacastro@portofguam.com, pagprocurement@portofguam.com

NOTICE TO OFFERORS: The IFB Documents of the above referenced project are hereby amended to now read:

- 1. Amend to Change Bid Schedule provide in original bid packet and also to replace the bid schedule provided in Addendum No. 3. Please see the attached and latest and final Bid Schedule for this project.**
- 2. All others remain the same.**

***** END OF AMENDMENT NO. 3*****

Issued by:

RORY J. RESPICIO
General Manager

NAME OF PROPOSER:

AUTHORIZED SIGNATURE:

PRINT NAME:

DATE:



PORT AUTHORITY OF GUAM

Jose D. Leon Guerrero Commercial Port 1026 Cabras Highway, Suite 201, Piti, Guam 96925

Waterline Replacement Commercial Port, Piti, Guam

BID SCHEDULE

Item	Description	Qty.	Units	Unit Price	Amount
A	GENERAL				
1	Administrative Submittals	1	LS		
2	Permits and Bonds	1	LS		
3	Mobilization & Demobilization	1	LS		
4	Close-out Documents	1	LS		
B	DEMOLITION				
1	Safety Fence and Traffic Controls	1	LS		
2	Demolish Bituminous Pavement	1357	SY		
3	Demolish Concrete Pavement	1560	CY		
4	Disposal of Demolished Materials	2012	CY		
5	GPR Scanning for Existing Underground Utilities	102	EA		
6	GPR Scanning for Pipe to be Abandoned	67	EA		
7	Excavation for Pipe Abandonment Window	267	EA		
8	Flowable Fill for Pipe Abandonment	450	CY		
9	6" Diameter Plug for Pipe Abandonment	48	EA		
10	10" Diameter Plug for Pipe Abandonment	208	EA		
11	12" Diameter Plug for Pipe Abandonment	62	EA		
12	16" Diameter Plug for Pipe Abandonment	216	EA		
13	Industrial Hygienist Consultant for Asbestos Pipe Abandonment	1	LS		
14	Handling and Disposal of Asbestos Containing Material	1	LS		
15	Floating Barge for Removal and Replacement of 6" Diameter Water Later Under Concrete Deck	1	LS		
16	Removal of 6" Diameter Waterline Lateral under Concrete Deck	1	LS		
17	Cutting and Capping of Existing Waterlines	54	EA		
C	NEW WORK				
1	Erosion and Sedimentation Controls	12325	LF		
2	Earthwork, including Excavation, Bedding, Backfill, and Disposal of Excess Materials	12325	LF		
3	6" Diameter PVC Pipe, including fittings and other appurtenances	880	LF		
4	12" Diameter PVC Pipe, including fittings and other appurtenances	8210	LF		

5	16" Diameter PVC Pipe, including fittings and other appurtenances	2500	LF		
6	6" Diameter Ductile Iron Pipe, including fittings and other appurtenances	570	LF		
7	6" Diameter Gate Valve, including fittings and other appurtenances	31	EA		
8	12" Diameter Gate Valve, including fittings and other appurtenances	22	EA		
9	16" Diameter Gate Valve, including fittings and other appurtenances	4	EA		
10	Air Relief Assembly, including fittings and other appurtenances	4	EA		
11	Tapping to Existing Lines	39	EA		
12	Restoration of AC Pavement including friction course	4070	LF		
13	Restoration of Concrete Pavement	1514	CY		
14	Restoration of 4" Thermoplastic Paint on Pavement	4070	LF		
15	24" Water Manhole Cover	2	EA		
TOTAL BID AMOUNT					